


Schedule of Accreditation

issued by

United Kingdom Accreditation Service

21 - 47 High Street, Feltham, Middlesex, TW13 4UN, UK

 Accredited to ISO/IEC 17025:2005	Osprey Concrete Testing Limited	
	Issue No: 001 Issue date: 20 July 2011	
	Birchall Lane Cole Green Nr. Welwyn Garden City Hertfordshire SG14 2NR	Contact: Mr D Foulger Tel: 07920 027123 Fax: E-Mail: doug.foulger@djmconsulting.org Website:
Testing performed by the Organisation at the locations specified below		

Locations covered by the organisation and their relevant activities

Laboratory locations:

Location details	Activity	Location code
Address Birchall Lane Cole Green Nr. Welwyn Garden City Hertfordshire SG14 2NR	Local contact Mr D Foulger	Aggregates Concrete
		A

Site activities performed away from the locations listed above:

Location details	Activity	Location code
All locations suitable for the activities listed	Mr D Foulger	Concrete
		B



4663
Accredited to
ISO/IEC 17025:2005

Schedule of Accreditation
issued by
United Kingdom Accreditation Service
21 - 47 High Street, Feltham, Middlesex, TW13 4UN, UK

Osprey Concrete Testing Limited
Issue No: 001 Issue date: 20 July 2011

Testing performed by the Organisation at the locations specified

DETAIL OF ACCREDITATION

Materials/Products tested	Type of test/Properties measured/Range of measurement	Standard specifications/ Equipment/Techniques used	Location Code
AGGREGATES	Particle size distribution - sieving method	BS EN 933-1:1997	A
CONCRETE - fresh	Sampling - composite sample - spot sample	BS EN 12350-1:2009	B
	Slump	BS EN 12350-2:2009	B
	Determination of flow	BS EN 12350-5:2009	B
	Air content – Pressure method	BS EN 12350-7:2009	B
CONCRETE - hardened	Making test cubes and curing	BS EN 12390-2:2009	A
	Compressive strength of cubes (loads from 50 to 2000 kN) - including curing	BS EN 12390-3:2009 BS EN 12390-2:2009	A
	Density	BS EN 12390-7:2009	A
END			